Poster prepared for:



Do not cite or distribute without author's permission

Effects from pile driving operations on harbour porpoises at Horns Reef offshore wind farm, monitored by T-PODs and behavioural observations

Jakob Tougaard¹, Jacob Carstensen¹, Henrik Skov², Jonas Teilmann¹ and Oluf D. Henriksen^{1,3}.

1) National Environmental Reseach Institute, Frederiksborgvej 399, DK-4000 Roskilde, Denmark

2) DHI Water and Environment, DK-2970 Hørsholm, Denmark

3) DDH Consulting, DK-4000 Roskilde, Denmark




Pile Driving and Mitigations

Monopiles were driven into the seafloor, generating very high sound pressures. Each operation took between 30 minutes and 2 1/2 hours


Mitigations used to prevent damage to marine mammals:

- Ramp up of impact energy
- Deployment of pingers (broadband 50-200 kHz signal, 153 dB re. 1 μ Pa @ 1m) and seal scarer (10 kHz signal, 170 dB re 1 μ Pa @ 1 m) about 30 minutes prior to each operation.


Behavioural Observations



Visual observations from ship along line transects were carried out on days with pile driving and days without pile driving. Behaviour of porpoises were separated in four categories: Directional movement, non-directional movement, logging (resting at the surface) and porpoising (fast swimming).



Behaviour on days without pile driving dominated by nondirectional swimming (possibly feeding) No significant difference with distance to wind farm



Significant shift towards directional swimming on days with pile driving (c^2 = 21.3, P < 0.001). Behaviour significantly different with distance to wind

The Porpoise Detector (T-POD)



Acoustic datalogger that records clicks from harbour porpoises.

Sensitivity 100-200 meters, highly specific for porpoise signals

Deployed inside and outside the wind farm area during construction period.

Three stations (#1, #6 and #7) provided usable data on days with ple driving.

T-POD Recordings


Time between encounters recorded on T-PODs were analysed.

Mean waiting time without pile driving: 44 minutes (n = 1709)

First waiting time after pile driving (time from end of operation to first encounter was significantly longer: 4.5 hours (n = 91)

Second waiting time (from first to second encounter) was not significantly different from mean waiting time outside pile driving operations.

Effect was seen on all three positions.



Second waiting time after ramming

| Policy | Po

Conclusions

- Porpoises clearly affected by pile driving operations, evidenced both by changes in acoustic behaviour and surface behaviour
- Initial reaction to pingers/seal scarer likely (and desired!)
- · Reaction seen across entire reef (T-PODs)
- Rapid recovery 2-3 hours after end of each operation
- T-POD powerful tool for impact study.

References (available at www.hornsrev.dk):

Tougaard, J., Carstensen, J., Henriksen, O.D., Skov, H., & Teilmann, J. 2003: Short-term effects of the construction of wind turbines on harbour porpoises at Horns Reef. - DDH-Consulting, Roskilde, Denmark, 72 pp.

Tougaard, J., Carstensen, J., Henriksen, O.D., Teilmann, J. & Hansen, J.R. 2004: Harbour porpoises on Horns Reef – effects of the Horns Reef wind farm. National Environmental Research Institute, Roskilde, Denmark, 69 pp.

Acknowledgements: This study was financed by the Danish National Energy Authority and Elsam Engineering A/S. It forms a part of the National Demonstration Project on Offshore Wind Farms

Thanks are due to skipper and crew on survey ships as well as observers.